BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division,
Schedule - B

NAME OF WORK: Construction of R O Plant in ward no 14

Sl.No	Description of work	Unit	Qty	Rates Quoted by Contractor Nagesh V (SREE RANGA ENTERPRISES)	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earth work excavation for foundation of building water sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of colds complete as per specifications	Cum	22.30	326.96	Rupees Three Hundred Twent Six and Ninety Six Paise Only
2	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	4.74	5769.83	Rupees Five Thousand Seve Hundred Sixt Nine and Eigh Three Paise O
3	Providing and constructing granite /trap/ baslat size stone masonry in foundation with cement mortar 1:6, stones hammerd dressed in courses not less than 20cms high, bond stones at two m apart in each course including cost of materials, labour, curing complete as per specifications	Cum	16.88	5046.22	Rupees Five Thousand Fo Six and Twen Two Paise O
4	Providing ruled pointing to coursed stone masonry with cement mortar 1:3 20mm deep, after raking joints to depth of 20mm necely lining, including cost of materials, labour, curing complete as per specifications	Sqm	15.50	159.46	Rupees O Hundred Fi Nine and Fo Six Paise O

Signature of the Contractor

Executive E
Dasarahalli

5	Filling avaialble excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms in depth compacting each deposited layers by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specification.	Cum	22.30	219.79	
6	Providing and laying in position reinforced cement concrete cum of Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super piasticisers @ 3 liters confirming to IS 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspiliars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications.	Cum	1.85	6749.59	Rupees Six Thousand Seven Hundred Forty Nine and Fifty Nine Paise Only
7	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, for coping. Including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	1.04	6027.34	Rupees Six Thousand Twen Seven and Thir Four Paise On
8	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	0.18	77601.32	Rupees Seve Seven Thousa Six Hundred and Thirty T Paise Only

ture of the Contractor

Executive E
Basarahalli

	Providing and removing centering shuttering strutting propping etc., and removal of form work for sides and soffits of beams beam houchings cantilever girders bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specification	Sqm	12.33	319.3	Rupees Three Hundred Nineteen and Thirty Paise Only
10	Fabrication supplying and erecting M.S. tubular trusses of all spans as per approved drawing & design with prefabricated steel applications using quality material and are durable, reliable and corrosion and abrasion resistant. Welding shall confirm to latest structural welding code. Quality shall be on various parameters like shape, size, design gauge and polish. The entire trusses is anchored in RCC column by using 4 nos of M.S. anchor bolts at each support with 10mm thick t| base plate and shoe plate. The work includes cutting, straightening, placing in position of M.S. pipes and welding wherever necessary and applying one coat of redoxide primer coat to all the members including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and lift, transportation, letc., complete as per specification.	Nos	780.18	121.38	Rupees One Hundred Twen One and Thirt Eight Paise Or

Exec
Dasa

Signature of the Contractor

11	Providing and fixing self-supported, ribbed, high quality, high grade (D.350 MPA Yst Min), pre- painted Galvalume steel roof sheet, coated with bare Galvalume coating A Z 150, @ 150 gms/Smtr 55%AL,45%Zn) by hot dip process, of total coated thickness as specified for different spans with a tolerance of +/- 0.02 mm, according to technical specification confirming to A 792, with NCCA 11-1, or ECCA T4 Pencil hardness HB, NCCA standard T-Bend test The roof should be fastened to the gutter beam, on the external sloping side, at an interval of 51mm Centre to Centre,to a depth of 65 mm with GI anchor bolts and neoprene washers & subjecting the gutter beam to Schmidt Hammer test to ensure the anchorage of the anchor bolts. The self-supported roofing system should be designed to with stand the wind load (As per IS 875 part-3) & Earthquake load (as per IS 1893) & the design should also comply with any other technical requirements such as turbo ventilators of 0.60 mts dia and skylights of size 4.26 x 0.60 mts. fixed one in each row @ 10.00 Mtr C/C along the length & hangers for electrical fixtures as per the requirements including cost of all materials &labour for erection, all lead and lift, loading and unloading, HOM of machineries etc.,	Sqm	86.22	2389.3	Rupees Two Thousand Thr Hundred Eigh Nine and Thir Paise Only
12	Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips; suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & pull operations complete including pulling hooks, 4Nos. handles with all fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications.	Sqm	6.25	2850.75	Rupees Two Thousand Eigh Hundred Fifty and Seventy Fi Paise Only
13	Providing and fixing top covers made out of 20 guage M.S. sheet over pull and push rolling shutters bent to shape including cost of red lead primer coat of painting , materials, labour, HOM of machinery complete as per specifications.	Sqm	2.50	527.07	Rupees Five Hundred Twen Seven and Sev Paise Only

ignature of the Contractor

Executive Eng
Dasarahalli Di

	Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering. Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications	Sqm	21.12	320.2	Rupees Three Hundred Twen and Twenty Pai Only
15	Providing and laying flooring using prepolished, water cut/gang saw 19mm thick granite laid over bed of 20mm thick 1:4 cm & jointed with neat cement slurry mixed with pigment to mach shade of granite slabs including laying POP on finished surface and cleaning the surface, including the cost of all materials and labours etc., complete as per specifications. - using silver grey granite / Multy Red / Ruby Red / Black / HassanGreen Granite of width not less than 900mm (P.No.110, I.No.14.47.2 of PWD SR 2018-19)	Sqm	32.48	2636.27	Rupees Two Thousand Six Hundred Thirt Six and Twent Seven Paise Or
16	Providing, fabricating, assembling and fixing in position aluminium partitions using aluminium sections of mat finish or glassy finish in combination of plain grove, single grove and double grove as per requirements for the frames of overall size 63.5mm x 38.1 mm. with thickness of 2mm. having section weight, plain sections 1.054kg/m, single grove thickness 1.95mm section weight 1.094kg/m double grove thickness 1.9mm section weight 1.094kg/m and bottom member 114.3 mm x 44.45mm. thickness 3.18mm. weight 2.646 kg/m; aluminium louvres section of size 36. 5mmx34.93mm 1.45mm. thick section weight 0.429kg/m; bottom portions provided with 12mm thick prelaminated sheet both sides of approved colour lamination exterior grade upto G.9m height, spacing of vertical member not exceeding 0.6 m. c to c; sections are cut to the required lengths, joints mitered and corners grinded subdividing frames tennoned and rivetted to the frames; the assembled frame stiffened with corner angles, stripped and fixed with screws, rawl plugs and teak wood gutties to R.C.C.columns on sides, R.C.C. lintels or beams at top and floor at bottom, including cutting chistelling and making good with cement mortar to match	Sqm	5.67	3678.53	Rupees Thre Thousand Si Hundred Seve Eight and Fif Three Paise O

Signature of the Contractor

Executive
Dasarahal

17	Providing, fabricating, assembling and fixing in position aluminium doors using following aluminium mat finish or glossy finish, outer frame plain section 101.6x44.45mm thickness 3.18mm, section weight 2.404 kg/m, door shutters vertical section 44.62x44.45mm thickness 3.18mm, section weight 1.505kg/m, top section 47.62x44.45mm thickness 3.00mm, section weight 1.426kg/m bottom section 114.3x44.45 thickness 3.18mm, section weight 2.646kg/m, door central section 49.91x44.45mm thickness 3.00mm, section weight 1.495 kg/m glazing clips 19x17.3x11mm thickness 0.9mm section weight 0.124kg/m; aluminium sections cut to length joint metred cornersgrinded, the shutters pivoted opening arrangement with heavy duty aluminium alloy automatic door closures floor mounted, providing and fixing standard approved accessories, such as aluminium handle for full width or length, tower bolts, lock, pivots; P.V.C. or rubber gasket with 5.5m thick plain glass for top and bottom panel; aluminium sections treated for removal of any rust and prevention of further rust formation, and coated with greasy materials for non-adherance of mortars or any other sticky materials; the	Sqm	1.89	6704.25	Rupees Six Thousand Seven Hundred Four and Twenty Five Paise Only
18	Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications.	Sqm	39.70	44.83	Rupees Forty Four and Eighty Three Paise Only
19	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	Sqm	39.70	103.88	Rupees One Hundred Three and Eighty Eight Paise Only
20	Water purification plants: Supplying, Installation andCommissioning of automatic Water purification plant (RO+UF)with all accessories piping, product water tank on single phase power supply on Turnkey/EPC Basis as per the enclosed detailed Technical Specifications including cost of material, loading and unloading and as directed by the Engineer in charge	Nos	1.00	405000.0	Rupees Four Lakh Five Thousand Only

Signature of the Contractor
Name of the Contractor

Executive Engineer
Dasarahalli Division

	Additional price for installation of Ultra Voilet system	Mtr	1.00	10125.0	Rupees Ten Thousand One Hundred Twenty Five Only
2	Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications	Mtr	1.00	7466.42	Rupees Seven Thousand Four Hundred Sixty Six and Forty Two Paise Only
3	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 20mm nominal OD pipes. (P.No.96, 1.No. 13.86.2 of PWD SR 2018-19)	Mtr	30.00	256.97	Rupees Two Hundred Fifty S and Ninety Sev Paise Only
4	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 25mm nominal OD pipes.	Mtr	20.00	320.4	Rupees Thre Hundred Twen and Forty Pai Only

Executive En
Basarahalli Di

25	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) - 32mm nominal OD pipes	Mtr	20.00	408.97	Rupees Four Hundred and Nine Paise
26	Supplying heavy gauge PVC conduit pipe ..... dia mm thick confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.19/20mm dia 2mm thick	Mtrs	40.00	50.63	Rupees Fifty and Sixty Three Paise Only
27	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments 1.5 Sqmm	Mtrs	70.00	20.76	Rupees Twenty and Seventy Six Paise Only
28	2.5Sqmm	Mtrs	50.00	32.4	Rupees Thirty Two and Forty Paise Only
29	4.0Sqmm	Mtrs	20.00	45.56	Rupees Forty Five and Fifty Six Paise Only
	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0 sqmm (Earth wire) FRLS multi strand PVC insulated copper wire (confirming to IS-694 and latest amendments) without control switch shall be fixed on the existing plastic sheet/ gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block complete for each outlet.Short point upto 3Mtr from tapping point to out let via switch box	Point	4.00	162.0	Rupees One Hundred Sixty Two Only

e of the Contractor.

Signature of the Contractor.

Executive Engineer
Dasarahalli Division

31	Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch box	Nos	2.00	253.13	Rupees Two Hundred Fifty Three and Thirteen Paise Only
32	Long point above 6Mtr upto 10Mtr from tapping point to out let via switch box	Nos	1.00	379.69	Rupees Three Hundred Seven Nine and Sixty Nine Paise Onl
33	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall. 1-3Way	Nos	3.00	96.19	Rupees Ninet Six and Ninete Paise Only
34	16-18Way	Nos	2.00	182.25	Rupees One Hundred Eight Two and Twen Five Paise On
35	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. 1 to 3 Module	Nos	3.00	111.38	Rupees One Hundred Eleve and Thirty Eig Paise Only
36	16-18 Module	Nos	2.00	273.38	Rupees Two Hundred Sever Three and Thir Eight Paise Or
37	Supplying and fixing of modular switch & connected accessories on exsting modular switch plate as per IS 3854 and IS 1293. 6Amps one way Switch (1 No-3.6.1)	Each	2.00	70.88	Rupees Seven and Eighty Eig Paise Only
38	6Amps 3way socket (1 No-3.6.3)	Each	2.00	106.31	Rupees On Hundred Six Thirty One Pa Only
39	16Amps one way switch (1 No-3.6.8)	Each	2.00	116.44	Rupees On Hundred Sixt and Forty Fo Paise Onl
40	6/16Amps universal socket (1 No-3.6.11)	Each	3.00	164.03	Rupees On Hundred Si Four and Th Paise On

Executive
Dasarahall

41	1000-1200Watts Dimmer (I No-3.6.7)	Each	6.00	[illegible]	[illegible]
42	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.6-32 Amps DP (Page No -27, I No-5.17.4 of electrical PWD S.R 2019-20)	Each	2.00	920.36	[illegible]
43	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 12 mm dia	No	2.00	3037.2	Rupees Three Thousand Thirt Seven and Twenty Paise Only
44	SSupplying & fixing of Porcelain fuse channel with cut outon existing wooden/panel using necessary nuts, bolts and washers. 16Amps	Each	1.00	118.46	Rupees One Hundred Eighteen and Forty Six Paise Only
45	Supplying & Fixing retrofit type -PL- LED lamp..... W LED Linear source with CCT 6500 degree K, CRI> 70%. Efficacy >80 lumen per watt, life> 25000 burning hours and Compliance to IS 10322/IEC 60598, LM 79 & LM 80. The LED are driven by HF electronic diver integrated in the system, with PF > 0.95, Power loss should < 5% of lamp wattage., short circuit & open circuit protection to be integrated in the circuit, THD less than 20%, life as per LM 79. The operating input voltage should be between 130 to 275 volts. Tested by NABL/CPBI accredited laboratory with 2years Warranty against any manufacturing defect working under standard electrical 18-20 Watts.	Nos	5.00	430.31	Rupees Four Hundred Thirty and Thirty One Paise Only

[illegible] of the Contractor,

Executive Engine
Dasarahalli Divisi

46	Fixing all types and all capacities of fluorescent / false ceiling / spot light / CFL / LED fittings indoor on the wall / ceiling / rafters / girders using 23/0.0076" twin twisted PVC insulated wires, required Nos of round blocks and clamps On wall / ceiling / Rafter / Girders	Nos	5.00	111.38	Rupees One Hundred Eleven and Thirty Eight Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,